

土木工事積算基準（令和元年11月）の一部修正その1 新旧比較表

現 行（Ⅱ-7-11）	修 正	備考（内容）																																																																																																																																																																																																																								
<p>(3) 構成人員 軽量金属支保工設置及び撤去の班編成人員は、次表を標準とする。</p> <p>表4-4 軽量金属支保工班編成 (1班当り)</p> <table border="1" style="width: 100%; border-collapse: collapse; text-align: center;"> <thead> <tr> <th>名 称</th> <th></th> <th>土木一般 世話役</th> <th>とび工</th> <th>普通作業員</th> <th>計</th> </tr> </thead> <tbody> <tr> <td rowspan="2">腹 起 し 材 (軽量金属)</td> <td>設 置 工</td> <td>1</td> <td>1</td> <td>3</td> <td>5</td> </tr> <tr> <td>撤 去 工</td> <td>1</td> <td>1</td> <td>3</td> <td>5</td> </tr> <tr> <td rowspan="2">切 梁 材 (水圧式パイプサポート)</td> <td>設 置 工</td> <td>1</td> <td>1</td> <td>3</td> <td>5</td> </tr> <tr> <td>撤 去 工</td> <td>1</td> <td>1</td> <td>3</td> <td>5</td> </tr> </tbody> </table> <p>(4) 軽量金属支保工施工歩掛</p> <p>表4-5 軽量金属腹起し材 (片側延長200m当り)</p> <table border="1" style="width: 100%; border-collapse: collapse; text-align: center;"> <thead> <tr> <th>名 称</th> <th>設置段数</th> <th>設 置</th> <th>撤 去</th> </tr> </thead> <tbody> <tr> <td rowspan="3">土木一般世話役 (人)</td> <td>1段</td> <td>0.4</td> <td>0.3</td> </tr> <tr> <td>2段</td> <td>0.8</td> <td>0.6</td> </tr> <tr> <td>3段</td> <td>1.3</td> <td>0.9</td> </tr> <tr> <td rowspan="3">特殊作業員 (人)</td> <td>1段</td> <td>0.4</td> <td>0.3</td> </tr> <tr> <td>2段</td> <td>0.8</td> <td>0.6</td> </tr> <tr> <td>3段</td> <td>1.3</td> <td>0.9</td> </tr> <tr> <td rowspan="3">普通作業員 (人)</td> <td>1段</td> <td>1.2</td> <td>0.9</td> </tr> <tr> <td>2段</td> <td>2.4</td> <td>1.8</td> </tr> <tr> <td>3段</td> <td>3.9</td> <td>2.7</td> </tr> </tbody> </table> <p>表4-6 軽量金属切梁材 (片側延長200m当り)</p> <table border="1" style="width: 100%; border-collapse: collapse; text-align: center;"> <thead> <tr> <th rowspan="2">名 称</th> <th rowspan="2">設置段数</th> <th colspan="2">水圧式パイプサポート</th> </tr> <tr> <th>設 置</th> <th>撤 去</th> </tr> </thead> <tbody> <tr> <td rowspan="3">土木一般世話役 (人)</td> <td>1段</td> <td>0.2</td> <td>0.2</td> </tr> <tr> <td>2段</td> <td>0.4</td> <td>0.4</td> </tr> <tr> <td>3段</td> <td>0.7</td> <td>0.6</td> </tr> <tr> <td rowspan="3">特殊作業員 (人)</td> <td>1段</td> <td>0.2</td> <td>0.2</td> </tr> <tr> <td>2段</td> <td>0.4</td> <td>0.4</td> </tr> <tr> <td>3段</td> <td>0.7</td> <td>0.6</td> </tr> <tr> <td rowspan="3">普通作業員 (人)</td> <td>1段</td> <td>0.6</td> <td>0.6</td> </tr> <tr> <td>2段</td> <td>1.2</td> <td>1.2</td> </tr> <tr> <td>3段</td> <td>2.1</td> <td>1.8</td> </tr> <tr> <td rowspan="3">水 圧 ポ ン プ タンク水量15~19 L (台)</td> <td>1段</td> <td colspan="2">4.0</td> </tr> <tr> <td>2段</td> <td colspan="2">4.3</td> </tr> <tr> <td>3段</td> <td colspan="2">6.0</td> </tr> </tbody> </table>	名 称		土木一般 世話役	とび工	普通作業員	計	腹 起 し 材 (軽量金属)	設 置 工	1	1	3	5	撤 去 工	1	1	3	5	切 梁 材 (水圧式パイプサポート)	設 置 工	1	1	3	5	撤 去 工	1	1	3	5	名 称	設置段数	設 置	撤 去	土木一般世話役 (人)	1段	0.4	0.3	2段	0.8	0.6	3段	1.3	0.9	特殊作業員 (人)	1段	0.4	0.3	2段	0.8	0.6	3段	1.3	0.9	普通作業員 (人)	1段	1.2	0.9	2段	2.4	1.8	3段	3.9	2.7	名 称	設置段数	水圧式パイプサポート		設 置	撤 去	土木一般世話役 (人)	1段	0.2	0.2	2段	0.4	0.4	3段	0.7	0.6	特殊作業員 (人)	1段	0.2	0.2	2段	0.4	0.4	3段	0.7	0.6	普通作業員 (人)	1段	0.6	0.6	2段	1.2	1.2	3段	2.1	1.8	水 圧 ポ ン プ タンク水量15~19 L (台)	1段	4.0		2段	4.3		3段	6.0		<p>(3) 構成人員 軽量金属支保工設置及び撤去の班編成人員は、次表を標準とする。</p> <p>表4-4 軽量金属支保工班編成 (1班当り)</p> <table border="1" style="width: 100%; border-collapse: collapse; text-align: center;"> <thead> <tr> <th>名 称</th> <th></th> <th>土木一般 世話役</th> <th style="background-color: #cccccc;">特殊作業員</th> <th>普通作業員</th> <th>計</th> </tr> </thead> <tbody> <tr> <td rowspan="2">腹 起 し 材 (軽量金属)</td> <td>設 置 工</td> <td>1</td> <td>1</td> <td>3</td> <td>5</td> </tr> <tr> <td>撤 去 工</td> <td>1</td> <td>1</td> <td>3</td> <td>5</td> </tr> <tr> <td rowspan="2">切 梁 材 (水圧式パイプサポート)</td> <td>設 置 工</td> <td>1</td> <td>1</td> <td>3</td> <td>5</td> </tr> <tr> <td>撤 去 工</td> <td>1</td> <td>1</td> <td>3</td> <td>5</td> </tr> </tbody> </table> <p>(4) 軽量金属支保工施工歩掛</p> <p>表4-5 軽量金属腹起し材 (片側延長200m当り)</p> <table border="1" style="width: 100%; border-collapse: collapse; text-align: center;"> <thead> <tr> <th>名 称</th> <th>設置段数</th> <th>設 置</th> <th>撤 去</th> </tr> </thead> <tbody> <tr> <td rowspan="3">土木一般世話役 (人)</td> <td>1段</td> <td>0.4</td> <td>0.3</td> </tr> <tr> <td>2段</td> <td>0.8</td> <td>0.6</td> </tr> <tr> <td>3段</td> <td>1.3</td> <td>0.9</td> </tr> <tr> <td rowspan="3">特殊作業員 (人)</td> <td>1段</td> <td>0.4</td> <td>0.3</td> </tr> <tr> <td>2段</td> <td>0.8</td> <td>0.6</td> </tr> <tr> <td>3段</td> <td>1.3</td> <td>0.9</td> </tr> <tr> <td rowspan="3">普通作業員 (人)</td> <td>1段</td> <td>1.2</td> <td>0.9</td> </tr> <tr> <td>2段</td> <td>2.4</td> <td>1.8</td> </tr> <tr> <td>3段</td> <td>3.9</td> <td>2.7</td> </tr> </tbody> </table> <p>表4-6 軽量金属切梁材 (片側延長200m当り)</p> <table border="1" style="width: 100%; border-collapse: collapse; text-align: center;"> <thead> <tr> <th rowspan="2">名 称</th> <th rowspan="2">設置段数</th> <th colspan="2">水圧式パイプサポート</th> </tr> <tr> <th>設 置</th> <th>撤 去</th> </tr> </thead> <tbody> <tr> <td rowspan="3">土木一般世話役 (人)</td> <td>1段</td> <td>0.2</td> <td>0.2</td> </tr> <tr> <td>2段</td> <td>0.4</td> <td>0.4</td> </tr> <tr> <td>3段</td> <td>0.7</td> <td>0.6</td> </tr> <tr> <td rowspan="3">特殊作業員 (人)</td> <td>1段</td> <td>0.2</td> <td>0.2</td> </tr> <tr> <td>2段</td> <td>0.4</td> <td>0.4</td> </tr> <tr> <td>3段</td> <td>0.7</td> <td>0.6</td> </tr> <tr> <td rowspan="3">普通作業員 (人)</td> <td>1段</td> <td>0.6</td> <td>0.6</td> </tr> <tr> <td>2段</td> <td>1.2</td> <td>1.2</td> </tr> <tr> <td>3段</td> <td>2.1</td> <td>1.8</td> </tr> <tr> <td rowspan="3">水 圧 ポ ン プ タンク水量15~19 L (台)</td> <td>1段</td> <td colspan="2">4.0</td> </tr> <tr> <td>2段</td> <td colspan="2">4.3</td> </tr> <tr> <td>3段</td> <td colspan="2">6.0</td> </tr> </tbody> </table>	名 称		土木一般 世話役	特殊作業員	普通作業員	計	腹 起 し 材 (軽量金属)	設 置 工	1	1	3	5	撤 去 工	1	1	3	5	切 梁 材 (水圧式パイプサポート)	設 置 工	1	1	3	5	撤 去 工	1	1	3	5	名 称	設置段数	設 置	撤 去	土木一般世話役 (人)	1段	0.4	0.3	2段	0.8	0.6	3段	1.3	0.9	特殊作業員 (人)	1段	0.4	0.3	2段	0.8	0.6	3段	1.3	0.9	普通作業員 (人)	1段	1.2	0.9	2段	2.4	1.8	3段	3.9	2.7	名 称	設置段数	水圧式パイプサポート		設 置	撤 去	土木一般世話役 (人)	1段	0.2	0.2	2段	0.4	0.4	3段	0.7	0.6	特殊作業員 (人)	1段	0.2	0.2	2段	0.4	0.4	3段	0.7	0.6	普通作業員 (人)	1段	0.6	0.6	2段	1.2	1.2	3段	2.1	1.8	水 圧 ポ ン プ タンク水量15~19 L (台)	1段	4.0		2段	4.3		3段	6.0		<p>職種の変更</p>
名 称		土木一般 世話役	とび工	普通作業員	計																																																																																																																																																																																																																					
腹 起 し 材 (軽量金属)	設 置 工	1	1	3	5																																																																																																																																																																																																																					
	撤 去 工	1	1	3	5																																																																																																																																																																																																																					
切 梁 材 (水圧式パイプサポート)	設 置 工	1	1	3	5																																																																																																																																																																																																																					
	撤 去 工	1	1	3	5																																																																																																																																																																																																																					
名 称	設置段数	設 置	撤 去																																																																																																																																																																																																																							
土木一般世話役 (人)	1段	0.4	0.3																																																																																																																																																																																																																							
	2段	0.8	0.6																																																																																																																																																																																																																							
	3段	1.3	0.9																																																																																																																																																																																																																							
特殊作業員 (人)	1段	0.4	0.3																																																																																																																																																																																																																							
	2段	0.8	0.6																																																																																																																																																																																																																							
	3段	1.3	0.9																																																																																																																																																																																																																							
普通作業員 (人)	1段	1.2	0.9																																																																																																																																																																																																																							
	2段	2.4	1.8																																																																																																																																																																																																																							
	3段	3.9	2.7																																																																																																																																																																																																																							
名 称	設置段数	水圧式パイプサポート																																																																																																																																																																																																																								
		設 置	撤 去																																																																																																																																																																																																																							
土木一般世話役 (人)	1段	0.2	0.2																																																																																																																																																																																																																							
	2段	0.4	0.4																																																																																																																																																																																																																							
	3段	0.7	0.6																																																																																																																																																																																																																							
特殊作業員 (人)	1段	0.2	0.2																																																																																																																																																																																																																							
	2段	0.4	0.4																																																																																																																																																																																																																							
	3段	0.7	0.6																																																																																																																																																																																																																							
普通作業員 (人)	1段	0.6	0.6																																																																																																																																																																																																																							
	2段	1.2	1.2																																																																																																																																																																																																																							
	3段	2.1	1.8																																																																																																																																																																																																																							
水 圧 ポ ン プ タンク水量15~19 L (台)	1段	4.0																																																																																																																																																																																																																								
	2段	4.3																																																																																																																																																																																																																								
	3段	6.0																																																																																																																																																																																																																								
名 称		土木一般 世話役	特殊作業員	普通作業員	計																																																																																																																																																																																																																					
腹 起 し 材 (軽量金属)	設 置 工	1	1	3	5																																																																																																																																																																																																																					
	撤 去 工	1	1	3	5																																																																																																																																																																																																																					
切 梁 材 (水圧式パイプサポート)	設 置 工	1	1	3	5																																																																																																																																																																																																																					
	撤 去 工	1	1	3	5																																																																																																																																																																																																																					
名 称	設置段数	設 置	撤 去																																																																																																																																																																																																																							
土木一般世話役 (人)	1段	0.4	0.3																																																																																																																																																																																																																							
	2段	0.8	0.6																																																																																																																																																																																																																							
	3段	1.3	0.9																																																																																																																																																																																																																							
特殊作業員 (人)	1段	0.4	0.3																																																																																																																																																																																																																							
	2段	0.8	0.6																																																																																																																																																																																																																							
	3段	1.3	0.9																																																																																																																																																																																																																							
普通作業員 (人)	1段	1.2	0.9																																																																																																																																																																																																																							
	2段	2.4	1.8																																																																																																																																																																																																																							
	3段	3.9	2.7																																																																																																																																																																																																																							
名 称	設置段数	水圧式パイプサポート																																																																																																																																																																																																																								
		設 置	撤 去																																																																																																																																																																																																																							
土木一般世話役 (人)	1段	0.2	0.2																																																																																																																																																																																																																							
	2段	0.4	0.4																																																																																																																																																																																																																							
	3段	0.7	0.6																																																																																																																																																																																																																							
特殊作業員 (人)	1段	0.2	0.2																																																																																																																																																																																																																							
	2段	0.4	0.4																																																																																																																																																																																																																							
	3段	0.7	0.6																																																																																																																																																																																																																							
普通作業員 (人)	1段	0.6	0.6																																																																																																																																																																																																																							
	2段	1.2	1.2																																																																																																																																																																																																																							
	3段	2.1	1.8																																																																																																																																																																																																																							
水 圧 ポ ン プ タンク水量15~19 L (台)	1段	4.0																																																																																																																																																																																																																								
	2段	4.3																																																																																																																																																																																																																								
	3段	6.0																																																																																																																																																																																																																								